

Argive Heraeum

ATH



1928

11

11

11

11



Apphia J. Hack
argue Heraclum
1928

Joints VIII. pages 96, 99, 102, 104, 106, 108, 109,
110, 112, 114, 115, 116, 117, 119, 120, 126,
140, 165, 168, + Book II page 19

Summary Book II. page 27, 28, 29, 30, 31, 32

Joints IX pages 90, 92, 94, 95, 98, 100, 101, 103, 105, 107, 111,
113, 118, 121, 123, 128, 133, 134, 137, 142

Summary page 21, Book II

22
23
24
25
26

Joints XXXIV pages 27, 31, 34, 35, 36, 45, 46, 51, 53, 54, 55,
72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 81, 84, 82,
84, 85, 86, 87, 88, 91, 97, 127,

Summary - page 59, 60, 61, 62, 63, 64.
Book I

Joints XXXV pages 13, 18, 41, 43, 130, 132.

Summary pages 65, 66. Book I

Joints XXXVI pages 9, 16, 17, 19, 20, 21, 22, 23, 24,
25, 26, 28, 30, 32, 33, 37, 42, 44, 47, 48, 50, 52.

Summary, pages 56, 57, 58.
Book I

Joints LII pages 122, 124, 125, 129, 135, 139,
157.

Summary pages 178, 179, 180 Book I

Shift grave trenches E XIX pages 146, 147, 148, 149, 150,

151, 152, 153, 154, 155, 156, 159, 160, 161, 166, 170, 173,

174, Cutting above S. Stoa pages 152, 153, 159.

Summary Book II. pages 33, 34, 35, 36.

Shift graves. Temple Terrace pages 158, 162, 163, 164,

167, 169, 171, 172, 173, 174, 175, 176, 177,

181, 182, 183, Book II page 20.

Summary pages 37, 38, 39 Book II.

Myc. grave (?) pages 90 (top), 93, 96, 143

Summary page 40 Book II.

Middle Helladic grave XIII pages 38, 49 Book I.

grave XIV page 39, 49 Book I

2

3



Tuesday April 24, 1928

Tomb XXXVI

4 men continue to clear loose earth on right have reached .60 soil reddish - finding several pieces of medieval pottery - also several fairly large sherds of geometric

Before noon took down part of disorderly dirt wall between door and Trench -

fairly large stones appear near dirt wall slightly to right depth 0.32

These taken out by men after lunch before our return

clearing then begun to right of probable cist leaving wall 0.30 between new clearing and earlier.

Earth toward trench becomes black at depth of .80 numerous sherds geometric

1 piece ^{broken} orange wire with knots square section length 32
1 piece ^{small} orange wire length 14.3 cm. diameter .08

at depth of 1.25 m. found a probable cist several small fragments of mycenaean sherd

1 flat circular ^{micaceous} button? with hole diameter 0.00.7 diameter of button 0.03.5 - sides slightly convex brown stone

small group of bones uncovered back and left of

continue page 16

(10)

"Hole in the ground"

April 24 Tuesday
 1 man continues to find outline of small arch west of narrow upright slabs.

on right piece of small pit .45 below top of slabs soil on right greenish resembling shales but soft. toward center whitish particles

outlines on left of the curves and center arch cleared to depth of 1.10 by noon

in front of slabs N.E. uneven rectangular space cleared to depth of .90 below top of slabs

digging in to depth of fairly regular curved outline uncovered maximum height by night

from floor = 1.17



width from upright slabs = 1.72

"Hole in the ground"

(11)

April 24
 Tuesday

125 cm width at rock door



(12)

4 figs
5 pigs

Tuesday April 24

Tomb XXXV

afternoon central cist uncovered to
depth of 0.20 m center. toward front 1 figurine,
2 small pigs, 1 cup.

toward back 1 beaker with figurine lying
across, 2 figurines, 1 pig

April 25, Wednesday Tomb XXXV

x central cist and 3 uncovered others filled with
water. this bailed out and work continued
on central cist. shell with half pt inner and under
a figurine - crystal bead 0.005 sq. 2 pierced shells 0.5 x 0.3 long

left front cist uncovered - nothing found

right cist uncovered
small pig, long bones

left back cist uncovered further
1 figurine
2 skulls

Earth removed for sifting

see page 18

(13)

April 24
Wednesday

(14)

Wednesday April 25, 1928

2 men digging trench little E. of north
from for short time.

(15)

April 25
Wednesday

(16)

From page 1
Wednesday, April 25.
Tomb XXXVI

men digging to right and take down remainder of wall of trench, trying to find outline of possible chambers

1 piece twisted and broken bronze wire length 0.40

- 1 oval piece bronze wire - broken evidently from another piece
- 2 bits straight bronze wire (0.03.7) x 0.01.4

numerous fragments of iron in black earth at right averaging from 0.03 long x 0.00.7 to 0.11 x 0.02

By noon line of fairly large irregular stones appear at depth of 0.60 (large one on right edge) with slightly curving line

layer of blackish earth which began at depth of 0.80 is 0.34 deep

Shards (geometric) in earth at right

Digging in wider area to right and beyond trench begun

- 1 bronze pin - length 0.05.5 - head diameter 0.00.5

see page 17

Thursday April 26.

Tomb XXXVI

4 men working on continuation of clearing earth in front of line of large stones which now shows, at either end, ^{the} beginning of another line at angle of about 95°

in front of main line of stone small round jug found at depth of 0.50 below top of highest stone. Broken

1 broken infant feeding bottle
1 round pot with handles

this may be side chamber of tomb. Not removed for sifting

clearing of area to left of possible side chamber begun.

cave like mass of stones may be door width 1.35 between two large stones. cave mass continued page 19

(17)
April 26
Thursday

Thursday, April 26 - continued from page 13

Tomb XXXV

Tomb measured and drawn by Miss Cox

Articles removed from central cist.
one piece of gray unpainted frog found
at outer end of cist. the other pieces at
inner end.

Pot no. 5 removed from right cist.

Bones removed from right hand and

left inner cist. Squirrel removed from
left inner cist.

Measurements of cists when cleared

Left outer 0.50 long, 0.45 wide, 0.30 deep

Central cist

Left inner 0.15 deep, 0.42 wide, 0.55 long

Right 0.60 long, 0.42 wide, 0.25 deep

Central 0.84 long, 0.30 wide, 0.20 deep.

Tomb cleared - April 26


see page (41)

Tomb XXXVI

from page 17
in front and between them
over joints and door?

(19)
April 26

Thursday



see page 24 for drawing

stones appears at 0.23 at left of
possible fallen door.

see page (20)

(20)
Friday
April 27

from page (19)

Lomb XXXVI.

4 men cutting down area between
XXXX and XXXVI.

By noon line of stones to left and back
of possible door appears. also line
of ruins back of
(also oval mass of stones) (joint?)
another line of stones to right of
possible door and back of joint(?)

Distance between 2 edges 2.05

1 button of reddish green ^{steatite} found 0.40 distant
from back wall directly in front of pat.
and 0.40 to left of bones. double concoid
+ reddish steatite button - double concoid
large diameter 0.01.7, small 0.00.7 - length 0.01.4
bits of paste beads

two cists begin to be outlined

inner one shows bones and skull(?)

1 red brown button - right end - steatite
concord
long diameter 0.02
small diameter 0.00.8
diameter of hole 0.00.4
length 0.01.2



1 reddish button - steatite
long diameter 0.02.7



work now being done with knives by

3 men

see page (21)

Lomb XXXVI. from page (20)

west
in ~~outer~~ cist bits of paste beads

2 carved ^{paste} stone head 0.01.7 long
Diameter 0.00.8 in center, 0.00.3 at ends



1 pendant paste heads 0.02.5
pear shaped 0.00.7
thickness 0.00.5



1 round head diameter 0.00.4

several large pieces paste poor condition

1 paste bead 0.02 diameter
0.01.4 thick



1 long paste head (broken) 0.03.4 long,
0.03.9 diameter



these cists appear to

1 black steatite button - chipped

1 round blackened bead 0.00.8 long
0.00.9 diameter

1 small burned bone

327 { 1 reddish black steatite button

1 large red button 0.03 long
0.03.2 large diameter
0.01 small diameter

1 long glass bead - damaged 0.02.5 long
0.01.4 diameter
see page (22)

(21)
Friday
April 27

22) April 27. Friday from page (21)

Tomb XXXVI

numerous small sherds found. (myc.)

4 pots uncovered by night

in sifting many broken pieces of bone

2 carved paste bead found near chimney
0.01.6 long
0.00.7 center diameter
0.00.3 end diameter

area behind possible door to back wall
from wall begun to be cleared and knife
work begun on front.

1 piece of steatite black.

It now seems apparent that the
left and right area separated by stones
may be combined to form one large tomb
chamber. If so, the top completely done -
mass of bones appear at left + back of
left area
see page 23

Saturday, April 28

Tomb XXXVI

1. Man sifting and
2 men working with knife and brush
in left area of tomb chamber. Later

they take out back line of stones and
pick down on right to level of bones
and pots on left. This done to try
to get definite outline of tomb
chamber.

1 piece of bone implement found in
further sifting of dirt from left
area.

0.03.6 long
0.01.2 diameter at pierced end
0.00.4 diameter at narrowing end
0.00.6 diameter of hole



However, lump of stones appears
back of another possible door - length 0.70
x 0.30, and 0.10 high.

possible door = 0.70 long
0.50 wide
0.35 high

Pots in left area - numerous


Pots in right area "

No bones as yet found in right area
two tombs? One tomb and side chamber?

(24)

Saturday April 28
Jamb XXXVI

scale 1 sq. = 0.20



mass of bones near of chamber is
approximately 0.20 above floor level

see page 25

Monday, April 30

Jamb XXXVI

(25)

Two men continue, with knives to
clear left area. * Bronze knife in
poor poor condition found.

1 man sifts earth from right area.

part of paste head found at back
of left area ^{later} numerous pieces of paste heads


1 carved paste head 0.01.5 long
4 sides - each side 0.00.6 wide at center
diameter at ends 0.00.3

1 round paste head - diameter 0.00.5

1 round paste head - diameter 0.00.8

1 steelite button - diameter 0.02.6

1 flat paste head with 4 flutes -
0.02.2 X 0.02.1
0.00.7 thick
2 pieces



1 pendant paste head (broken) 0.02.5 long

1 large round paste head (broken) 0.02 diameter

1 sq. =
1 centimeter

* bronze knife removed. blade in two
pieces. handle of wood or ivory with
bronze rivet. blade tapers to a point.
width 0.00.3

blade 0.18.3 - Handle at south west
from point to break 0.05.8
" break to handle 0.03.5
handle 0.04.4

beginning of handle to rivet 0.1.1

rivet to top 0.03.

diameter of rivet 0.00.3 see page 26



(26) Monday, April 30 Tomb XXXVI.
 From page 25
 In removing dagger blade separates into two
 pieces and handle breaks off into several
 pieces.

width of knife at base 0.01.8
 width of handle 0.02

see page 28

Monday, April 30
 Tomb XXXIV. From M. Marion Rawson
 Seven men continue to clear dromos.
 Two men work with knives in chamber.

1 large unpainted jug uncovered.


1 small jug uncovered near center of entrance

1 large bone back of door near bronze bowl
 (see M.R.)

In the middle of afternoon bones of
 animal (?) uncovered. ~~Found~~^{at} about center
 of chamber. Dirt near bones removed
 for rifling. Bones are 1.25

below surface of lowest point of chamber,
 and 1.65 below point directly above them

see page 31



(28)

Monday April 30 ^{from page 26} Tomb XXXVI

Sawed end of afternoon, a large mass of ^{paste} approximately 0.06 long much covered with dirt found in about center of left area near skull

By night ^{four} ~~three~~ small figurines,
1 fig with three figurines under
base
1 round bowl with holes in sides
are uncovered. also two bits of bronze

see page (30)

(29)

Monday, April 30

Stone

Middle Helladic grave ^{XIII} in front of Tomb XXXIV again uncovered. (was covered with earth from chamber of XXXIV)
Slabs removed. 2 large; 1 small.

Bones running S. to N. by E and two small jug appear by afternoon

The two large slabs were not over what is evidently the main burial. but lay with south end over part that probably will be feet.

see page (38)

(30)

Tuesday, May 1 from page (28)

May 1 3 men with knives continue to work floor of left area.

- Early morning, were found in addition to broken (bits of paste)
- 1 pendant paste bead - broken
 - 1 paste bead cylindrical diameter 0.015 (broken)
 - 1 round paste bead (broken) " 0.01
 - 1 cylindrical paste bead - 0.03 long x 0.01 diameter
 - 1 round hard bead dark yellow diameter 0.007
 - 1 " " amethyst (?) diameter 0.007
 - 1 round bead amethyst diameter 0.009
 - 1 " " " 0.01
 - 1 brownish steatite button - diameter 0.019 x 0.017
 - 1 dark purple bead round - diameter 0.007

Figurine, found on floor, face down, head to left on floor removed.

- length 0.077
- shoulder width 0.028
- diameter of head 0.019
- diameter at foot 0.02
- 1 crystal bead round diameter 0.008

C.W.B took photograph of west area

Higher mass of bones measures 1.10 m from back wall

directly in front and about below higher mass of bones, a large cist begins to be outlined in this are more bones, with skull.

another fairly large jug in west wall appears. So loose stones A on plan page 24 cut away.

Stairs extends 1.40 from South or outer line of stones to cist.

see page 32

(31)

Tuesday, May 1 from page (27)

May 1 2 men with knives continue to clear floor of chamber.

6 men work on dromos.

Foreman reaches Stairs on either side of door.

small jug uncovered 0.90 from outer line of chamber

3 fairly large plectrums (myc.) and several small found in dromos.

Floor of dromos reached at depth of 2.20 from top stone of door.

Height of door from ground surface 3.55
Somb now measures 5.15 wide by 3.70 deep.

Level being cleared is approximately 1.80 above floor of dromos.

Directly to left of door a large bone, human? a little to right of door in 1.40 small jug
Bones of animal 1.40 from back wall a little to left of door.

Inward left of these, remains of human bones. see page (34)

Tuesday, May 1 from page (30)

Tombs XXXVI

1 small jar uncovered from under loose stones at west ~~middle~~ of west area on floor.

Fallen door = 1.05 wide

all loose stones from door (now certain) to west wall cut away with knives.

this left or west area may now without doubt be said to be the main chamber and the right or east area a side chamber. the sides ^{of left} are straight, the back narrows in a curve.

at outer end stairs was reached at 0.75 below top stone of door and extends in 1.60. on this floor are two pots & figurine and a few bones.

the side door ~~measures~~ 0.65 above this floor and is 1.00 wide ^{at top}. It begins 1.10 ^{from front door}.

the line of stones across chamber breaks ^{at} 0.40 from west wall and a small cist with bones appears. small bone on straight line of stones appears on upper level. ^{East} larger cist with bones and skull und. appears 1.50 from back wall

see page 33

Tuesday, May 1 from page (32)

Tombs XXXVI

two jars, one with ^{two} ~~three~~ figurines under base and four separate figurines lie front and back of this larger cist on same level as front stones. at the back a large mass of bones extends all across the chamber. Bronze knife page 25 found at east side. fourteen pots in all shown on surface.

narrow trench 0.50 in front of door and extending about 0.70 to either side begun. a few shreds found. stones reached at 0.50 - 0.60 below surface.

see page (37)

(34) Tuesday, May 1 from page (31)

Tomb XXXIV

0.80 to right of small jug 2 more animal bones.
almost against East wall small outhouse
a large wine jar on their sides, turned
right back of chamber.

Dromas measures 1.80 wide at door at top
and 1.85 at floor.

~~Dromas~~ measures 0.95 at top 1.00 at floor

Dromas measures 1.60 at outer end.
men had cut away 0.50 at right + in

1.85 toward door beyond actual steros
~~the~~ outer large jug has round flat
piece of pottery - is it a cork?
(later no)

see page (35)


Wednesday
Tomb XXXIV from page (34)

(35)

3 men working, clearing floor
level.

May 2

Human skull is uncovered 0.40
to left of inner line of animal bones,
0.90 from west side of chamber.
and 1.00 from back - badly damaged.



— 1 sq = 0.20


see page (36)

(36)

Wednesday from page (35)

Somb XXXIV

May 2 a band of red soil 0.30 from floor of
Oromos runs straight across door embedded
 in loose earth which forms a gap 0.30 high
 beginning 0.25 above floor.
 1 sq. = 10 centimeter



A-B = line of reddish soil 0.00.4 wide
 area CDEF = soft earth - no stones in front -
 C.W.B. photographs Oromos afternoon
 C.W.B. photographs chamber to show
 two large figs.

Three men work down level of
 floor all day -

line of stones appears, running from
 South East corner to ^{right} front of animal house
 see page 45

from page (33)

Wednesday May 2 (37)

Somb XXXVI

2 men continue to work clearing
 earth from door. one man shifts
 earth taken from west area. 1
 they also begin to cut down earth
 out from trench (page 33)

Oromos is 1.84 wide
 chamber is 1.97 "

Door is 1.20 wide

a number of sherds found (1 piece at
 least of yellow Mnyan), others L.H. III.
 Shards reached at 2.10 ^{South} from door at
 depth of 0.20 below surface

slab 0.06 thick, in
 0.45 high
 0.25 wide

is uncovered at left of door

Two men now work with knives
 trying to find outline of cist
 or chamber to the East.

It seems to be cist outlined
 with fairly large stones.
 from door it measures 0.70 deep
 1.2 East to west and 2.00
 wide see page (42)

(38)

May 2 Wednesday

May 2

M.H. Grave XIII.

1 man continues to clear bones.
The skull is badly damaged.
The skeleton seems to be lying slightly
turned to left side in cramped
position.

cist now measures 0.45 deep
1.40 long
0.60 wide

one jug exposed at left of skeleton
on line with shoulder. also

one cup - mug? also at left on
line with elbow. Left femur shows.
Right arm shows entire, the left to
elbow only. only one leg bone to be seen.
Skull points south west.


C.W.B. takes photograph - morning.

Earth sifted - a few small bones
found and replaced in grave.
see page (49)

May 2, Wednesday
Middle Holladay grave
XIV.

(39)

May 2



3 men remove
top slabs covering
grave.

1 man deep outlines of cist
finds bones at depth of 0.50

By mid afternoon only 2 small
pieces black & yellow painted Matt
were found. and one small sherd.

By night - cist measures 0.65 deep
at west end, 0.50 at east end, 0.55 wide
1.28 long

No bones found. Presumption is
that grave had been robbed.



1 sq = 10 cm.

grave runs east to west. The few
bones lie 0.60 from west end 0.20
from each side.

(40)

May 2

Wednesday, May 2
Middle Helladic grave XII.

cist 0.60 wide
1.90 long
0.20 deep at north side
0.60 deep on south side

Skeleton lies East to West with skull,

badly damaged at East end. Bones of

pelvis seem to lie flat, legs turned

to right side, in bent position, left leg
over the right.

Total length 1.38

Length of femur 0.38

Length of tibia 0.32

One man clears these bones with knife and
brush and finds nothing.A.T.H. - begins to remove bones
and finds nothing.From page (18)
Wednesday, May 2 Tomb XXXV

(41)

May 2

Floor level of chamber is approximately
1.20 above upper level (back)
of Tomb XXXVI.

Is there another level in Tomb
XXXV?2 men sift earth (Page 13)
and find one small sherd.

see page (43)

(42)

May 2

From page (37)
Wednesday, May 2.

Somb XXXVII

Both the East and West sides are
now cleared for photographs and
drawings.

C. W. B. takes photographs of
a) Door,
b) East or side chamber.

Miss Cox measures tomb preparing
to drawing.

see page (44)

Thursday, May 3

Somb XXXV

From page (41)

May 3

- 1 man finishes sifting earth
finds four seeds
- 1 piece twisted bronze wire 0.02 long
- 1 shell 0.05 long, diameter at
greatest width 0.02.5

see page (43)

(44)

May 3

From page (42)

Thursday, May 3

Jamb XXXVI

Mrs Cox draws chamber.

A.T.H. removes figurines and pots

#3, #5

Under ^{sample of} Pot #3 found 1 brownish
steatite button 0.02 long1 workman begins to remove bones and
sherds.outer skull measures 0.9 x 0.15
found directly back of skull were

1 paste bead round diameter 0.02

1 " cylindrical - 0.03.3 long (broken)

1 pendant paste bead - 0.02.5 long (broken)

1 carved paste bead flat

1 piece bronze - bad condition 0.02 x 0.01.2

0.00.7 thick

1 pendant bead - broken

2 bits bronze wire 0.02.5 long

all dirt removed for sifting

in small cist at west wall (see page 32)

a skull appears

also a ^{bone} pot 0.70 from back wall and

0.40 from east wall

1 paste bead round 0.01.2

1 carnelian bead round diameter 0.02.5

1 round paste bead diameter 0.01.7

1 round flat paste bead

thick 0.00.3

1 broken steatite button diameter 0.00.9

long 0.02.5

1 flat paste bead similar to that on

page (45)

1 smashed paste bead

see page (47)

Thursday, May 3 From page 36

(45)

Jamb XXXIV

3 men working with knives cutting May 3
below floor level

fairly large Proto-Corinthian

pot in many pieces found 0.70

south of outer large jug.

four pieces of same found 0.30

back and 0.30 to left of small

outer pot.

In afternoon 5 men working

By night they have reached

level of 0.50 below floor and

of 1.40 at back of chamber

Bone 0.30 long - rib (C) appears

0.50 in front and 0.40 to right

of skull

see page (46)

(46)

May 4

from page (45)
Friday, May 4

Tomb XXXIV

Four men with knives continue digging down level of chamber floor

1. Cox draws Eastern area (where large pots are)

in afternoon draws western half of chamber

2 large bones appear. No. 20 long running

south from larger pile of animal bones

the second is 0.30 long and lies at

right angles 0.04 distant from first

nos. #1+2 large jars removed (amphora)

3 wine jar removed

4 small gray jar

5 2 red sherds

6 small cup found inside large jar #2

human jaw appears 0.50 ~~west~~ of inner amphora

1 very thin piece of bronze, seemingly $\frac{1}{2}$ of

a circular disc with hole 0.00.5 in center

Diameter of disc 0.06.5, appears 0.80 from

door - also several small pieces of same.

(afternoon session)

stones near amphorae and to right of door

removed.

Animal bones and two large bones to

left and right of door removed

see page (5)

from page (44)

Friday, May 4 Tomb XXXVI

(47)

May 4

1 man continues to remove upper stratum of bones and sherds -

By 8.30 7 more pots appear and ³ skulls, 2 bowls

1 man sifts dirt. 1 paste head

found in dirt (round) 0.00.8 diam.

2 cylindrical paste heads 0.04 long

both broken

4 pieces of paste

1 round paste head 0.00.9 diameter

1 flat round paste head 0.00.7 diameter
0.00.4 thick

1 flat round paste head 0.00.6 diameter
0.00.3 thick

green gray ~~steatite~~ button <TC button>
0.01.8 long, 0.01.9 wide

1 black ~~steatite~~ button - broken <TC>
0.01.2 long, 0.01.8 wide

1 round paste head 0.02. diameter

inner large skull removed measures
0.15 X 0.40

1 broken black ~~steatite~~ button
0.01.8 long, 0.02.3 wide

1 piece bronze between back wall
and skull - under bones

portion protruding from under bones
measures 0.10 - probably ^{same as} see page (48)

(48)

May 4

from page 47
 Sunday, May 4 -
 Tomb XXXVI

- 1 paste head carved in glutes in middle - knobs on either end
 0.01 long
 0.008 diameter in middle
 0.005 diameter at ends

2nd cleaning shards was found in bag

- 1 bone spool diameter at bottom 0.03
 diameter at top 0.02.2
 diameter of hole 0.01
 length 0.01.9

Between breakfast + luncheon were found

- 1 pendant paste head (broken) 0.02.4 long
 1 rounded paste head diameter 0.00.7
 1 round paste head - bent diameter 0.00.5
 1 flat paste head - diameter 0.00.6 thickness 0.00.4
 1 cylindrical paste head - (broken) long 0.03.5
 1 rounded paste head 0.02.2 x 0.01.6
 1 reddish steatite button 0.02.3 long x 0.02.9 wide
 1 black steatite button - chipped at narrow end
 0.02.2 long - diameter 0.02 (widest)
 1 black steatite button (chipped) 0.02 long
 diameter 0.02.2

2nd part of bronze tweezers (see page 46)
 both halves broken

length of one half 0.06
 length of 2nd half 0.06.6
 diameters at narrow end 0.00.7 and 0.00.5
 diameter at wide end 0.01.3

- 1 pale blue paste head 0.00.5 long 8
 spool shaped diameter 0.00.4
 1 greenish gray steatite button
 0.01.4 long - diameter 0.02.1
 1 flat blue black steatite button chipped
 0.00.5 thick, diameter 0.02.2
 see page 50

from page (38)


Friday

Middle Helladic grave XIII. 1 May 4

0.60 wide

1.40 long

1 sq = 10 centimeters



A.H. removes pots, and
 gathers bones -
 nothing found

(50)

May 4

Friday, May 4. from page (48)

Tomb XXXVI -

All sherds and pots removed and

all bones after

D. Cox has drawn them.


chamber now cleared and

2 men remove door.

after floor is cleared, the outlines of two
cists are definite.

see page 56

all bones replaced on floor.

1 cylindrical potsherd (broken) 0.02.5 long
found in sifting

see page (52)

from page 46
Friday, May 4, Tomb XXXIV -

(51)

May 5

Human skull, measures 0.18.07
X 0.14.6 removed.after removal of pots
and animal bones and skull, four
men continue digging with knives.

see page (53)

(52)

May 4

From page (50)

Sunday, May 4. Tomb XXXVI

Door to side chamber removed.

Miss Cox draws side chamber

The four pots removed (removed previously)

In main chamber, in addition to the large mass of bones, two skulls were found and small pieces of 15 more, 6 fragments, bronze tweezers, one bronze knife, 6 whole pots and remains of about twenty more.

In side chamber 5 pots were found.

For Summary see page (56)

From page (51)

Saturday, May 5 Tomb XXXIV -

(53)

May 5

4 men work with knives, two with baskets, cutting down floor. The level has now reached 0.90 below top of door.

Two large bones and rib (page 45) which lie on this level are left in place.

C.W.B. takes photograph of door at 4. metres.

Door removed to 1.50 above floor of dromos. Stones lie throughout from men then continue knife work on floor from to

In this first level the finds (amphora, jug, oenochoe, and bronze) were geometric. One Proto-Corinthian jug found.

Earth is now carried out through dromos.

One piece bronze found at spot where circular disc was found (page 46)

Door now taken down to 0.85 above floor level of dromos. at 0.90 above dromos but at left were found pieces of

see page (54)

(54)

May 5.

from page 53
Lomb XXXIV

cyls and one sherd of myc. fish net pattern. Stones at this level extend 1.10 in from front of door.

By room front of door is 0.25 below chamber floor level near door.

Two small animal bones appear 1.40

back of right side of door - removed

In the afternoon the large stones from door are carried away. The door

is taken down to 0.90 from floor of drums.

nothing more found in chamber by night

see page (55)

from page 54 Lomb XXXIV Monday (55)

4 men with knives and two May 7

with baskets continue to remove earth from chamber - a few sherds (myc) found.

skull with scattered teeth appears 3rd level lying on its right side, jaw to back wall 2.20 from right back wall in line with left side of door. 0.25 below 2nd level + 1.70 from west wall.

Bones on 2nd level human? 1.60 from back wall. 1.60 from left side of door



Bone A .26 long .0.05 at wide and 0.02.5 at narrow end.

Bone B .0.18 long X 0.03 wide.

Bone C .0.13 long X 0.05 wide

Bone D 0.15 long .0.25 to left of A

B.E 0.27 long. front 0.70 from front of A. back 0.55 from back of A.

Point F 1.35 from side wall.

In removing pile under there bones, many small shells and loose stones, fallen not placed found (72) see page

(56)

from page 52

Tomb XXXVI - Summary

Dromos

Length 2.95
 width at outer end 1.12
 width at inner end 1.84
 Sides vertical
 Depth of dromos at door 4.00
 inner angle 45°
 slope of floor

Door

width of jamb right 0.34 left 0.46
 width of door on floor
 inside 1.00
 outside 1.00

depth of door 0.64
 sides of door vertical
 Height of door 0.75

stones - small in general. one flat slab on left 0.45 high, 0.25 wide and 0.06 wide

Side Door
chamber

width of jamb (left) could not be defined

width of door on floor
 inside 0.90
 outside 0.93

depth of door 0.46
 sides of door vertical
 Height of door 0.65

Top of door - straight across
 stone wall closing door - small flat stones
 Two large stones at bottom on left.

Chamber - main

Length 3.40
 width at door 2.00
 at back 1.50

ceiling not preserved. floor 4.00 from surface
 corners right angles.

Across the entire width of chamber and extending out 1 meter and up 0.40 from level of floor was spread a mass of bones, skulls, sherds and pots. (Remains of 15 skulls). Scattered throughout this area - chiefly at right - were found: paste heads, steatite buttons, 1 bronze knife, 1 pair tweezers.

In front of this area lies a cist with rectangular niche at back and with a small oval cist cutting off its western South end.

Large cist measures 1.20 long (across chamber) (57)
 .50 wide and 0.22 deep
 niche cut out 0.60 from west wall, 0.25 from
 eastern edge of cist is from 0.20 to 0.35 deep

In this cist were found more paste heads and steatite buttons and bones and a few sherds.

The oval cist runs a little north of west 0.25 deep
 measures 0.53 X 0.26 and overlaps larger cist
 by 0.18. In this were found bones and one skull.

The larger cist is 1.55 from door.

On the floor were found four separate figurines
 2 pots (one with two figurines under handles) and
 a few bones.

Chamber - side to side 1.8. N. to S. 3.37
Side door to back 2.30
 ceiling lacking

no bones or pots were found at back
 or sides of chamber.

one cist, roughly outlined by stones
 at back and left side and by curved
 line of stones at right measures
 1.87 X 1.00 .05-.10 deep
 In this were 5 pots.

Inventory of Tomb XXXVI

- Pots L.H. II

many fragments paste heads

1 pair tweezers (bronze)

1 bronze knife

6 steatite buttons

1 bone spoon

1 cornelian bead

2 crystal bead

1 bronze pin

6 glass rings

3 amethyst beads

26 pots

17 shells
 pieces bronze (over)

(58)

In the main chamber
Here was no placed skeleton. The two pots
and four figurines and a few small
bones found near door were probably of
the latest burial.

The floor level of this tomb lies 1.20
below that of 35.

The surface of the rock slopes up a
little from level of 34 over 35 and 36 to

In main chamber toward front there was
a stratum of blackish ~~the~~ earth 0.34 deep
at level of 0.35 above floor. In this
were found bits of charred bone.

Tomb 36 lies 2.10 East of 35.

Inventory continued

- 10 Terra Cotta buttons
- 1 Terra Cotta weight
- 9 small pieces bronze
- 1 pierced bone implement
- 57. paste beads
 - 23 round
 - 11 cylindrical
 - 7 large flat
 - 1 broken
 - 1 small barrel
 - 5 pear pendants
 - 5 flat incised
 - 2 fluted (1 round, 1 flat)
 - 1 small double round
 - 1 glass pebble

Summary - Tomb XXXIX.

(59)

Dromos

length 9.50
width at outer end 1.20
width at inner end 2.00
slope of floor - gradual
sides - slight inward inclination
depth of dromos at door 3.20 from surface
inner corner - angle at
sheds. none

Door

width of jamb - Left side .55 Right side .50
width of door in floor
inside 1.05
outside 0.91
depth of door - Right side 1.86, Left side 1.84
sides of door slight inward inclination
top of door - shape - curves 30° left to center
height of door 2.20 then down 1.0 to right.

Stone wall along door - stones at front flat, back
rounded many fallen into chamber.
cylid stones 2 in door.

Chamber. depth - front to back 3.30
side to side 4.15

ceiling - fallen. a curve in rock begins
2.60 from floor. surface of ground 4.75 from floor.

Tomb 34. lies 3.80 East of Tomb 33. It is

cut into strata topped by thick ledge of
conglomerate. The floor level is 2.10 below
that of 35. The ceiling was fallen, making
digging down from above necessary throughout.
The chamber is rectangular; corners at back
right 45°, at front slightly curved. measures
4.75 from floor to surface of ground.

(60)

Dromos

Tomb 34

There is an inight beginning at door + running out 2.50 a ledge of stones 0.25 wide, and 0.20 high. on left of door and in center of dromos, steps rises gradually in a slope (height about 0.10). at first this depression was thought to be the dromos of an earlier and later chamber but floor level of chamber was found to be flush with this cutting.

The dromos runs at a slight angle to the chamber, ^{coming in off axis near right side of chamber smaller than} this may be explained by the presence of Tomb 52 which although at a

higher level is of earlier date than 34.

Dromos had gradual slope to the depression.

In the dromos were found many sherds.

2 mycenaean cylix stems in door.

The door was preserved to height of 2.20.

many stones had fallen into chamber.

The stones at front were flat laid in irregularly those at back were fairly large & rounded.

A line of reddish earth 0.04 wide run across door at height of 0.30. This line was later traced in right side of chamber and in cist under door.

Right hand postholes
0.18" for 0.50 from floor
and 0.30 wide.

(61)

Tomb 34

This probably indicated fumigation of some kind. (Traces of fire in chamber also noted later).

Chamber may be divided into four levels.

The highest level was geometric and was reached at 1.40 - 1.50 above floor level.

On this level were found

- 2 large amphora at back
- 1 wine jug
- 1 small gray jug
- 1 Proto-Corinthian jug
- 1 small cup (wide amphora)
- 1 bronze bowl
- 1 small bronze circular disc (near door)

The second level contained only the bones of a goat lying a little to the left line of door toward the back of the chamber, about 1.15 above floor level.

The third level contained an animal skull, an human skull and bones and lay about 0.90 above floor level.

The following finds were made about 0.50 above floor level near

Skull of 3rd level

- 1 stoneware button
- 1 shank of stoneware button
- 24 round Proto heads

See page (62)

(62)

June 34

- 1 carved paste head
- 7 broken paste heads

at height of about 0.40 to floor level were:

A heap of bones and ²⁰pots beginning at right back wall going to center of

chamber; extending 0.50 - 1.20 out from back wall

on floor level:

1. 1 placed skeleton lying near S. W. corner in contracted position - head to west lying on right side - arms in place ribs scattered, this probably the latest burial
2. 1 coarse red bowl 1.40 ^{back} from door
3. 2 bronze knives (one near skeleton, one between skeleton & heap of bones)
4. red pierced seal stone near skeleton
5. 1 bronze arrow head
6. 2 steatite buttons
7. 3 round paste heads
8. 4 obsidian arrow heads
9. 1 flint arrow head

5 cists and one niche were found;

cist I lies against anterior left wall

measures 1.20 X 0.60 X 0.30 - 0.50 deep

contained 10 pots, 1 I. H. I. sherd 2 skulls, large & small bones.

(63)

June 34

cist II lies against left wall (against part of niche between) cists I and III

measures 0.50 X 0.60 X 0.48 deep

Contained blackened (but not necessarily burned) bones.

cist III lies II to cist I, separated from it by cist II at left and

strip of steros on ^{right} measures 1.65

X 0.70 X 0.35 deep. Contained

2 pots, two skulls and bones.

cist IV runs 1.80 ^{along right wall} ~~deep~~ from

right front corner 0.70 - 1.00

wide X 0.25 deep. contained

15 pots and 2 skulls.

cist V full antleric completed only

when door fully removed as it

extended to within 0.50 of front

of door. measures 1.80 long X

0.70 wide X 1.20 deep. contained

2 pots, 1 skull and a few bones.

a niche outlined by six flat

stones is outlined in left wall beginning

in left front corner. measures 1.40 X

0.80 contained 10 pots and bones. sight over

slapping (64)

slapping (64)

(64)

Janis 34

from page (63)

right
in the heap at back of chamber on floor
level were found two small charred bones
and blackened earth was found at right of
cist IV.

The red line of earth in door was 0.30
above these other traces of fire.

Lying across line of stipes at a slightly
lower level than skeleton in S.W. was
another skeleton in place with head on edge
of cist III and leg bones ^{extracted} on edge of cist I.

Inventory:

- 61 Pots
5 Skulls
50 ~~24~~ round paste beads (47 round, 1 pear shaped, 1 fluted)
11 obsidian arrow heads
1 flint arrow heads
1 seal stone, (steatite)
2 bronze knives
6 steatite buttons (1 damaged)
1 bronze bowl (broken)
1 bronze disc (broken)
3 pierced shells
3 bronze arrow heads
1 bronze pin (5 pieces)
10 pieces bronze
7 broken paste beads

(65)

Summary - Tomb XXXV

Dromos

Length
width at outer end
width at inner end
slope of floor
sides
depth at door
inner corner angle

no dromos could
be defined.

Door

width of jamb

right side
left side

no jamb could be defined

width of door on floor

inside 0.78

outside 0.73 80

depth of door (front to back) — 0.80

sides of door

+ top of door — straight —

stone wall closing door. small flat stones laid in

height of door — 0.45 regular courses (3)

Tomb 35 lies 8:20 from right side of chamber of 52.

Chamber

width — 3.17

depth — 2.18 — sides curve gently to back

ceiling. lowest point of rock after it begins
to curve definitely, 1.35 from floor.

no real ceiling preserved. 7 in floor to surface — 3.10

Here are four cists

1. central directly 0.45 back of center
of door. 0.84 long, 0.30 wide 0.20 deep
remaining North to South.

contents

4 squarines

3 two small pins

1 cup

1 beaker

3 pierced shells

1 crystal head

2. Right — lies 0.40 to right and

0.40 back of door
measures 0.60 long X 0.42 wide 0.30 deep

(66)

Tomb XXXV

2. Right cist

contained - 4 long bones
1 small jug (No. 5)

3. Left outer. 0.70 from left of door on line
with it.
measures 0.50 long x 0.45 wide
x 0.30 deep.
nothing found

4. Left inner

measures 0.58 long x 0.42 wide x 0.15 deep.
contained 1 figurine,
2 skulls

Inventory Tomb XXXV

- 5 figurines
- 6 plates
- 2 skulls
- 1 crystal bead (?)
- 3 pierced shells
- 1 stentile bead
- 1 bit bronze wire
- 1 shell

It was thought at first that owing to the high
level of Tomb XXXV, in relation to XXXIV and
XXXVI that there was a lower level, but this could
not be ascertained. Tomb LIII is also at a high
level.

(67)

May 7

a Middle Helladic grave

114.50 directly in front (South)

of grave III was uncovered

1927. see Robinson notebook page 130.

The slabs were moved and small
stones removed. grave lies S.W.-N.E.
only one slab still in place.
Two men have removed one remaining

slab 0.90 x 0.63

Dig down in reddish soil to
depth of 0.40 and reach stones.
cist measures 1.40 x 0.65.

Later cist deepened 0.07 - 0.10 and
enlarged to 1.42 x 0.80.

Nothing found.

(70)
May 7

Monday

Middle Helladic grave
lies 6.50 to west of grave page 69

1 large stone 0.65 long, 0.30 wide, 0.35 high
1 smaller one standing upright removed
and two men dig down with picks

Stones reached at depth of 0.40

Cist (?) measure 1.00 X 0.60

nothing found

Monday

May 7 (71)

1 workman digs up earth directly

To South west of large stone placed 1.10

west of M.H. grave XI dug

1927. Stones found almost immediately

Stone 1.40 X 0.70 X 0.30 thick

removed. Stones again reached at

0.20

(12)

May 7

Monday from page (55)
 Tomb XXXIV.

Level XXXXIV

on 3rd level. directly back of human skull (page 55) appears 1 animal skull.

1 more ~~distance~~ ^{human feet} shall
first.

ribs and large flat bone to left and back of human jaw.

Monday. Jan 1 XXXIV
from page (72)

from page (72)

May 7 (93)

Front of chamber to right of door
cut away, leaving width of 1.05

Floor level by night reaches average
0.90 above floor level of drums.

Tuesday

May 8

James XXXX

4 men with knives and two with
baskets continue clearing floor of
chamber.

Skull - front to back measures 0.185. Front bone, however, crushed in a little - removed rib bones split in pieces.

In taking out animal skull, horns appear
both broken off - spread from tip to tip 0.21

Men are now working on level which may be called the 4^{th} -

1st level - amphorae and jugs
1.40 - 1.50 above floor level
of domos

2nd level animal bones 0.35 below
top of amphora

3rd level human jaw, human skull
+ animal skull 0.25 below 2nd level
1.2 - 0.90 above floor level of drums

Many loose stones found mixed in with all
this fallen stercos -

Earth around buns seems to be looser and reddish
see page (74)

(74)

May 8

from page (73)

Tuesday, Tomb XXXIV

next course of door stones cut away.
There are laid every across and back

Back stones smaller and rounder than front
ones which are fairly flat.

Door now reduced to 0.55 above floor
level of drums.

During afternoon a few sherds found near
door.

Left inside of door cut away to width of 1.10

see page (75)

from page (74)

Wednesday, May 9 Tomb XXXIV

(75)

May 9

4 men with knives and two
with baskets continue digging
down the chamber level.

Floor level now about 0.60-0.50 above drums floor
a few sherds found near door and to left
myl. 2 of octopus pot.

During morning many more sherds Myc?

found also

1 purplish steatite button
widest diameter 0.02.1

length 0.01.1

1 paste head - diameter 0.01.3

diameter of hole 0.00.4

length 0.00.7

1 round paste head

diameter 0.00.9

1 carved paste head.

4 uneven flints

length 0.01.4

diameter 0.00.8

1 chipped paste head

length 0.00.7

diameter 0.00.6

1 round paste head broken in halves

diameter 0.00.9

1 round chipped paste head

diameter 0.01.1

afternoon 218 whole paste beads diameter 0.00.9

75 broken "

these were found near ~~new skull~~
found in S.W. corner - lying S. to N.

with head at South. Skull cracked

1 shank of ~~dark~~ steatite button - green grey

length 0.01

widest diameter 0.01.7

narrow " 0.00.5



see page 76

(76)

from page 75 Wednesday

Jomb XXXIV

May 1

Dirt near skeleton set aside for sifting

found 5 bits thin bronze wire
lengths: 0.03.5, 0.06, 0.018, 0.01.7
& 0.015

1 ~~paste~~ paste head - round - diameter 0.00.8against west wall 0.60 from S.W. corner
on all pot.1 broken flat dish w. large red painted
handle to right of this small pot.1 bronze arrow head directly under
outer edge of skull
length 0.01.5, width 0.01.31 small red painted pot with
handles directly to right of broken flat
and to back of chamber.

1 red steatite button 0.01.3 long x 0.01.7

As more & more small bones appear, skeleton
north and above seems to a mass of bones in a
niche -

1 more pot appears -

skull turns out to be broken pot.

Wall now cut away making niche at left
side of door about 0.80 x 1.40Skull appears at left back wall (0.40 from
back - 0.60 from left wall). This may be
whole skeleton. This is about 0.40 above
floor of drums.1 green iridescent paste head - diameter 0.01.5
slightly flattened found in niche.This niche is outlined on chamber side
by line of 6 stones about 0.25 wide ^{high} 42By night 14 pots are visible and
2 skulls.

see page 77



from page 76 Thursday

Jomb XXXIV

(77)

May 10

4 men with knives and two with
baskets continue cutting down floor
level of chamber.On right side 3 pots appear
2 about 0.90 from back wall
and 1.10 from right.1 about 1.30 in from right
side of door.2 pots (broken) against back
wall 1.70 from right wall1 ^{flat} bowl (broken) 1.00 from
^{with handle} back wall and 0.45 from right
side.Boxes (one large) begin to appear
in front of 2 broken pots against
back wall.

Between breakfast & lunch

1 large stirring cup 0.90 from
back wall.

a good many sherds (muc)

1 paste head - round diameter 0.01.2

at the right back pots and bones
(no skull) seem to be thrown in a
mass.to the right of door - against right
wall a grave with skull and

see page 78

(78)

May 10

from page 77 Thursday Tomb XXXIV
5 two pots are outlined gradually. cist
measurements 2.00×1.00 , narrowing at inner end.

One skull ^{0.50} appears ~~in line~~, other to left of
left line of door is in about 1.60 from
front. Also a group of bones to right of skull
then reaching stairs at about 0.40 above
brass floor level. near door

22 pots visible by room
all but seven are badly broken.

Several large bones appear in cist 0.35 down
skull near door.

1 sq = 2 c.

Bronze ~~knife~~ ^{skull}, tip to wall 0.70 from back
wall. 0.15 from left wall
0.14 long, 0.015 wide at handle and 0.016 wide
at middle, tapers to 0.003 wide. 2 rivets, one
0.025 from handle end, other 0.01. In removing, breaks
across 0.06 from tip. 0.017 wide between rivets
Red pierced seal stone, plain on one side
curved from thin edge to center
found 0.70 from back wall 0.09 from
middle of knife

0.014 long at hole
0.016 greatest length
0.015 wide
0.005 thick



In cist at right 1 purplish gray steatite bottle
0.008 long diameters 0.005 and 0.014

see page 79





Tomb XXXIV

May 10

there are traces of fire in cist at
light near side wall, also near

bronze knife. two pieces charred bone
0.90 from back wall 0.92 from right wall.
By right 5 skulls show in right
cist, 41 pots in all

see page 80



(80) from page 79 - Fri day
May 11 Tomb XXXIV



4 men with knives - ² with
basket continue clearing chamber.
skeleton at left back (page 76)
is in place, lying on right side
head to left wall in contracted
position. arms in place & partial femur and tibia
Ribs scattered

Bronze knife, lying west to east, handle to west
1.05 from left wall, 0.15 from back,

0.18 x 3 long, 0.01 wide at handle end, 0.01.8
widest width, tapers to a point (chipped)
3 rivets - 0.05, 0.02.6, and 0.00.5 from
handle end.

Working in left side, during morning found
scattered small & large bones - 2 skulls

pots (1 stirring camp

2 paste heads - round - diameter 0.00.9
similar to those found in niche at left and
just outside of niche (page 75)

1 stone arrow head 0.02.6 long x 0.00.9 wide
obsidian


1 stone arrow head 0.02.8 0.01.4 wide
obsidian

By noon 5 more pots appear - left side
1 fragment I + II against left front wall

1 large fragment (late) in door way right.

1 obsidian arrow head 0.03.4 long x 0.01.3
wide - some obsidian see page 81

afternoon



from page 80



Tomb XXXIV

(81)
May 11

The placed skeleton at back and
scattered layer of bones and pots and
right back are about 0.40 from dromos
floor level. Bones on level line with
inner end of niche (page 78) are
slightly below back level.

Digging down at left between door + niche
another cist is being outlined - similar
to that on right.

The area of steros near door page 78
proves to be fallen.

at left again 1 obsidian arrow head
0.04 x 0.01.5

7 more pots visible

1 steatite button 0.00.8 long x diameter
0.00.6 and 0.01.4

1 flint arrow head point broken
02.05 long, 001.3 wide

a hole ca 0.60 deep, ^{extending} 1.00 deep

see page
81/2

(83)

May 12

Saturday Tomb XXXV

3 men start to remove heap of
earth piled in front of door - finish + clear

Saturday Tomb XXXIV from page 82 (84)

May 12

the height of back area corresponds
with height of thin red line in
soil in door noted on page 36.

This may mean that tomb level
below was fixed - charred bones found
on this level (page 79) 0.40

The skull and scattered bones in left
center (page 78) seem to be a little
below level of back skeleton.

these may be the latest interments.

1 man cleans up bones and pots.

Small piles of small bones removed.

area at right back can not as yet
be called a heap - too spread out.

Can all stereo area now left be
fallen and this level (0.40) be second
burials?

the line of red earth noted in page
36 can be traced in inner side of door
and in antechamber of hole in front of door
(chamber side)

May this mean that present floor see page 85

(85) From page 84. Saturday
Jomb XXXIV

May 12

level was filled in over earlier (smaller) chamber. otherwise why is lower floor level below floor level of chamber?

*

chamber is now ready for second lot of photographs and drawings.

chamber measures 4.15 wide x 3.15 deep with niche in left wall 0.80 wide x 1.40 ~~deep~~ ^{long} outlined by 6 stones.

In niche are visible 13 pots and small bones.

Cist I 1.20 x 0.60 (long end along front left wall) contains 2 skulls, large + small bones and 10 pots.
depth 0.50-0.30

Cist II about 0.50 x 0.60 against wall of niche between cist I + III contains

blackened bones in poor condition. (older?)
depth 0.40 below top of niche stones

Cist III runs parallel to cist I measures 1.65 x 0.70 - depth 0.35, contains 2 pots, a few large bones and 2 skulls.

Lying across cists III + I with head to back wall and about 0.15 below floor level is a skeleton in place. The femurs and pelvis are lacking but lower leg bones
see page (86)

From page (85)

Saturday, Jomb XXXIV

(86)

and feet; head and arms are in place. May 12

To right of this skull is another badly smashed with a few bones, large bones, however are gone.

at back wall on floor with head to left wall lies another skeleton in place. also smashed. but contracted leg position may be clearly seen.

extending along back wall from about center of chamber and width goes from 0.80 to 1.20

lies a mass of bones, 21 pots and two skulls. This is on floor level more

underneath probably. Two bits of burned bone found. (page 79)

Cist IV extends in 1.80 from right front wall and is 0.70-1.00 wide and 0.25 deep. The earth at outer right shows black. fire. Cist contains 20 pots and 3 skulls.

Separated from cist I by line of stones 0.40 wide and from cist IV by line of stones 0.30 wide lies a hole 0.60 deep, 0.70-0.80 wide (on

see page (87)

(87) Saturday, Tomb XXXIV from page (86)
May 12

line with door) and 1.00 long.
a few bones already found in this are they in
int or part of earlier chamber? Time will
tell.

1 small coarse red bowl lies on floor
1.40 from door and a little to right of middle
of door.

The area at right and back of chamber
seems to be drier than the rest. Can damp
line outline the earlier & smaller chamber?
It forms, roughly, a circle.

The Pottery, with the exception of one sherd
which is L. H. I., is L. H. III.

Dromos.

In front of door in dromos there is
a slight depression in the floor. This ^{low}
measures 1.00 wide (width of door) X 2.50
on the right the steros rises about 0.20
in a step. The width of this ^{portion of} steros is
0.25. on the left the steros rises gradually
to left wall.

This depression may indicate the width
see page (88)

from Page (87) Tomb XXXIV. Saturday (88)
May 12
of the original dromos - of a smaller
chamber.

The layer of fallen steros comprising
floor of exposed chamber would be made
from cutting a larger chamber.

Tomb XXXIV - Monday May 14
Miss Cox begins second part of drawing.

see page (91)

(89)

May 14

Monday.

Two men working.


In Trench 3.50 to west of geometric grave
at depth of 0.55 were found group of large bones
* and 1 Terracotta animal (Myk. also a number of
sherds (Myk) and several pieces of a cylix.
Then trials made a little east and west
of bones, trying to find a dromos. A few
more sherds found in each trench.

Later in afternoon a few Early Helladic appear
fairly near surface in western trench.

In eastern trench appear at depth 0.45
+ 0.30 from east side of trench + 0.30 from south edge.
jug () in poor condition - badly broken

~~from~~ see page (90)

- * From tip of nose to tail
animal measures 0.10 - 0.07.3 tall
It has both horns and ears - (probably a cow)
Decorations - undulating stripes of red and yellow



From page (89)
Tuesday

(90)

May 15

2 men continue work in trench
near geometric grave VIII.

1 man in trench to west. Find 2 sherds,
E.H. Long first trench deepened.

During morning digging further
uncovered + more bones including
skull belonging to group uncovered earlier.

(page 89) area measures 2.25 x 1.80 - length -
greatest depth 0.80 - smallest depth 0.40 - see page (93)

In long Trench 6.00 N.E. of bones
and 14.00 from ^{dromos of} south VII, a dromos

1.20 wide outlined - this to be known as Tomb VIII - later

Three men now follow this in toward IX

a small pile of stones in slope.
a few sherds and 1 piece 1 cm. 2.4 x 0.05 found.
see page (92)

(91)

from page 88 - Tuesday
Sunt XXXIV.

May 15

1 man sifts dirt.

Mrs Cox continues drawing of plan.

C. W. B. photographs

- Items no. 6. left cist from right wall
 7. Back right area from right wall.
 8. Back right area from west on floor
 9. left inner cist from floor
 10. Back placed skeleton

afternoon - man finds one obsidian arrow head
 length 3.06 - diameter 1.05

Mrs Cox continues drawing -

1 workman begins to remove pots.

May 16

Sunt XXXIV.

Mrs Cox continues drawing.

1 workman removes more pots and bones

C. W. B. - photographs

2 of right cist

amphora #34 filled with light gray ash.
 small box reserved for analysis

In removing pots & bones were found

- 3 pierced shells 0.04, 0.035, 0.03 long
 20 whole paste beads - round, diameter 0.009
 + fragments of same - similar to + here on
 page
 1 fluted paste bead 0.015 long, 0.005 wide
 1 broken " " 0.015 diameter.
 1 steatite button 0.015 long, diameter 0.022
 3 obsidian arrow heads 1.025, 0.032, 0.025
 long
 1 bronze arrow head (broken) 0.036 long, 0.011 wide
 1 " " 0.026 long, 0.017 wide
 4 tiny pieces bronze - tips of arrow heads

See page 95 (91)

From page 90 - Sunt ~~III~~ IX Wednesday (92)

May 16

2 men digging down in chert.

During morning - several large
 evidently placed stones 0.25 below
 surface appear. Between them
 and line of rock outlined ~~in~~ ^{to} ~~away~~

slope, the earth is dark, blackened
 at right. at left, at depth of 1.00
 and 2.00 from stones several
 bricks appear. when?


at depth of 1.10 and 0.45 from left
 wall a bronze mesomphale found.
 It is badly broken, many small pieces
 found, flaked off.
 measures 0.15 diameter, 0.025 deep.

The slightly curved outline of rock at
 back is from beginning of pile
 of placed stone. Are these stones the
 same? No

In afternoon another bronze
 flat bowl found 0.40 from right
 wall, 1.10 from back at depth at
 1.00. Removed whole. It is bent see page (94)
 forming an oval. Diameters 0.11.4 and 0.10.5

(93) Wednesday from page (90) top

May 16 scale 1:24 = 20cm



skull and fig. = 0.50 below surface.

Is this a grave?
see page (96)

drawn Tomb VIII

Wednesday - from page (92)

Tomb VIII - IX 3.40pm May 16

and 0.02.5 deep. (geometrie) ^{at door} at water end

a few geometrie sherds found. ^{drawn}

Two more men begin to clear
draws on western side of Trench.

a few pieces of iron found behind
door(?)

1 badly broken bronze bowl
0.12 diameter found in digging at
right wall, trying to find outline
of chamber. 2 Myc. sherds found

see page (95)


(95) Thursday - Tomb ~~VIII~~
IX from page (94)
May 17

2 men continue to dig out right
wall beyond ^{not placed above} door p slope (in chamber)
at depth of 1.05 on left - find badly
shattered small bronze bowl - one handle extant.



2 Terracotta spools 0.04 high - 0.03, 7 diameter
1 broken bronze cup - diameter 0.07, 1
height 0.05, 3
handle broken off 0.01, 4 wide

1 lead ring - bent. diameter 0.02, 5
straight piece 0.01, 7 x 0.00, 5 on top.
(geometric)



2 pits located at 0.50 ^{above dromos floor} near
left wall of dromos. 1.50 + 1.70 from left ^{door jamb}
several pieces iron found in chamber.
one handle end of sword 0.03 wide by
0.22 long -

Chamber later attacked from above -
By afternoon two men start to dig
dromos.

By night dromos is 4.70 long,
0.95 deep at door and 0.45 at outer end.

Stakes reached at sides and back
see page (98)

Thursday - from page (93) (96)
May 17

area enlarged to S.W. in
hope of finding meaning of these
bones - see page (143)

2 men begin clearing earth in
front of geometric grave VIII to left
and right in trial trench. Darker earth
in trench may be another dromos.

By noon location of another tomb fairly
certain - men dig in further toward
geometric grave VIII from trench.

This to be known as Tomb VIII and
the tomb to its left (north) changed
to tomb IX.

see page (99)

(97)

Thursday from page (91)

May 17 Tomb XXXIV

chamber now entirely cleared of
pots and bones.

In all levels 71 pots were found
13 skulls.

Two men begin to remove more of
door to 0.30 above dromos floor.
Then the whole door.

It is now seen ^(dromos near door dug out a little more) that the line of reddish
soil is about 0.10 above floor level of
chamber at back.

The remainder of the door is removed during
afternoon. 2 (myc.) sherds found.

The cist in front of door is dug out.

measures 1.80 long, 0.70 wide, 1.20 deep.
It extends to 0.50 from front of door.
It contained 2 pots (myc.) 1 skull
and a few bones.

The stones of the lower part of door were
large and flat at front, but at back were
roughly cut round stones.

see page (127)

Thursday - Tomb IX

from page (95)

(98)

May 17

The left side is fairly straight,
curving to back. Right side is
curved.

chamber ^{by night} ~~now~~ measures 2.30 x 2.00

see page (100)

(99)

Friday
May 18

Janr VIII. From page (96)

2 men continue digging dromos.
This dromos probably goes through
geometric grave VIII. ~~with~~ chamber
lying beyond under slope of hill.

By main door found at edge of and
a little below surface of geometric
grave VIII. Dromos is wide.

a quantity of Myc. sherds with
3 cylix stems found.

near door found

- 1 double conoid greenish steatite button
0.01.6 long, and diameter 0.00.9
middle diameter 0.01.5
- 1 single ~~best~~ conoid steatite button
0.01.3 long X 0.02.3 widest diameter
- 1 single conoid steatite button red
0.01.8 long X 0.02.6 diameter of base

By mid afternoon door is outlined and
cleaned. top stones missing. ^{Some fallen in front} at present
stones straight across top - small and
irregularly placed. Height 1.15; width at floor:

0.78 at top 0.60
Dromos at floor is 1.30 wide

at 1.42 from door is a step 0.10 high
and 0.40 wide. irregular outline

2nd step rises 0.10 above first

0.40 wide see page (102)

Friday Janr IX. From page (98)

(100)

May 18

Two men continue work in
dromos

Two men work in chamber.

Top ^{fallen} door stones cleaned

1.20 high from present floor level
1.00 wide 0.30 from surface
large and small irregularly cut stones

In chamber at right bronze ring
Diameter 0.01.2 with 0.00.5

Bronze flat bowl in many fragments
found in right outer corner of chamber.
very dark earth around it.

Several pieces of iron including
large ring 0.05 in diameter.

C.V.B. photographs stones from
end of dromos. Stones removed.

Door jamb on left outlined.
width .33

In dromos myc. sherds (2 cylix
stems) chamber still geometric.

102 2 pots in dromos 1.80 and 1.70 from
left door jamb (page 95) removed -
shattered.

1 bronze ring found in back of
chamber - diameter 0.02.4 see page (101)

(101)

Lomb VIII

From page 100 - Friday

May 18

1 Terra cotta spool 0.04.4 long
 diameter at ends 0.04.1
 " middle 0.02.2

During afternoon chamber enlarged.

Stones of yesterday was not stones

Drones finished. door cleared.

Length = 5.27
 width at outer end 0.79
 " inner end

at 3.20 from outer end on right a ledge
 appears 0.20 wide forming small step
 0.35 ^{high} deep. Rest of floor from this point
 uneven.

at left beginning directly in front of left jamb
 jamb lies a cist covered with eight flat
 stones. Depth below present top of door
 = 1.20. Depth below surface in middle
 of cist = 1.60 cist measures - 1.62 X 0.40

Two top courses overhang
 0.20.

Door high = 1.40
 width at top 0.60
 " floor 0.70
 depth = 70-80
 gradual inclination

See page (103)

From page (99) Lomb VIII Friday

(102)

May 18

2 men now begin to dig out
 drones beyond trial trench -
 finish drones.

length = 5.50
 width at outer end = 0.80
 " door 1.30
 depth of drones at door = 2.00
 first step begins 2.90 from outer end
 Door jamb right 0.33 at floor, ~~0.30 at top~~
 jamb left 0.33 at floor ~~0.30~~
 " width at floor
 " depth

sides incline ⁱⁿ beginning 0.80 from floor
 3 stones embedded in left door jamb

four men now begin clearing chamber
 from above. this area was geometric plane

VIII - at back of chamber floor = 2.80 from surface
 see of page (104)

(103)

from page (101)

Friday - Tomb IX

May 18

Left jamb width at floor - 0.32
 Right jamb " " " 0.20

Door is made up in front of fairly small
 stones irregularly placed. one large stone
 on lowest course.

1 small coarse red pot (handle gone) found
 (pot #3)
 1.20 above floor level

in right wall - diam. 0.07. height 0.07.5

1 bronze ring - narrow - 0.23 diameter
 (geometric)

see page (105)

from page (102) Saturday

Tomb VIII

May 19

(104)

4 men continue digging down
 chamber from above.

1 pot found 1.60 from front right
 wall. 0.30 from back, 0.30 from
 right wall. 1.30 from lower part
 of overhanging rock. geometric black
 top diameter 0.08
 base " 0.05.3
 height = 0.04.4

pieces of geometric bronze - rim
 of bowl 0.11.7 diameter

By breakfast general level = 0.20

below top of door.

Pieces of bronze disc 0.15 diameter
 found at back. on even level with top
 of door - embedded in fallen stones.

3 terracotta spools at right back
 all 0.04.2 high
 end diameter of two = 0.04
 1 = 0.03.6
 middle diameter = 0.02.2

C.W.B. takes photograph of door (#6)

door torn down 0.55 i.e. to 0.60

from floor of tomb and earth

see page (106)

(105)

from page 103 Saturday
Jamb IX.

May 19

Two men continue work in chamber -
enlarge it at back and right side.

Many ^{small} pieces of geometric bronze found -

By breakfast mean level of chamber is
0.60 below highest part of door.

C. W. B. takes photograph of door.

Pot (geometric) 1.00 from right wall, 1.00 from
front 0.40 below highest part of door

4 removed - diameter 0.20 - 0.02.2 thick

~~Door~~ Part of door removed. leaving height
of 0.70. Some of the stones are flat
(irregular shape) but most are fairly
round. all irregular.

5 small ^{black} geometric pot found 0.10 to right of ^{pit 4} floor

1 bronze pin with ^{double} knot length 0.07.5
1 " " " knot " 0.04.7

By night chamber floor is 0.30 below door.

Stones like not yet completed at back chamber
now measures 3.00 wide x 2.90 deep

see page (107)

Saturday Jamb VIII

from page (104)

(106)

new carried out in baskets end diam = 0.03. May 19
1 terra cotta spool 0.09.1 high middle " = 0.02.2

1 Bronze ring - decorated with piece
of bronze looped around it - joining
top -

1 bronze pin - point missing 0.07.3 long
(0.55)
at level flush with door - left side
is found bronze bowl - ring handle
which is broken off - diameter 0.09
deep - 0.02.

2 thin bronze discs - diameters
0.03 and 0.05.5

against left wall (in middle)

1 bronze bowl - diameter 0.11.4
depth 0.02.4

with raised portion in middle 0.03.5 diameter
on bottom 3 incised lines around middle
lines and crossers at top outside
on sides overlapping chevron pattern.

By night chamber floor flush with door
about 0.55 above dromos floor.

measures 3.38 wide x 2.42

see page (108)

From page (105) Monday
(107) Tomb IX
May 21

2 men continue to dig down
level of chamber floor -

just before breakfast one man taken
away & other comes to Tomb VII

In afternoon three men again at work.

(Later 4)

By night floor level about 0.6.0 above
bottom of door.

see page (111)

From page (106) Monday. Tomb VIII (108)
May 21

2 men continue to dig down
level of chamber. Two men
remove earth, (baskets). Still
working through fallen stones
a few sherds (glauconitic) ^{containing} found.
(Later 3 basket carriers) working.

By noon floor level cut down to
0.40 below present height of door -
nearly to floor level of dromos.

Base appears at right back. very firm
earth cut further back at right back.

Staircase base appears at front left.

2 small pots appear against right
wall middle - also 1 stentite button
0.00.6 long, wide diameter 0.01.3

Silt now removed for rifling & work
with knife. Find near grey pot

1 cylindrical paste head 0.01.4 long

X 0.01

5 cylindrical ^{olive pot shape} black paste heads

0.01.2 long X 0.00.7

1 cylindrical black paste head 0.01.5 X 0.00.6
^{olive pot shape}

see page (109)

May 21

1 round black paste head 0.00.5 diameter

During afternoon a niche is outlined
in right wall
and 1 skull, 2 jaws & 5 pots appear.

3 three kinds paste heads

21 black blue pit shape of various sizes

19 round paste heads 0.00.9 diameter

4 cylindrical " "

1 steatite button greenish gray
0.00.7 long x 0.01.4 inside diameter

1 dark steatite pendant ^{head} (shape of a pot)
0.01.5 long - pierced thru neck

1 yellow brown pendant of steatite
0.01.3 long

also 9 ring paste heads - a cushion type 0.00.3 long

Six large bones also outlined in niche

The heads were found scattered among bones.

They were not placed in conjunction with the skulls.

at the left front was over two pots (1 broken)
and 1 piece of a skull.

see page (110)



May 22

Two men continue to dig at
back wall - rectangular niche.

begins to be outlined at back.

knife work at right + back. During
morning 5 more pots and 1 skull
appears. also.

1 black steatite ^{pendant} head (pot shape)
pierced thru neck 0.01.2 long



1 greenish gray steatite pendant head
0.01.4 long - diameter 0.01.1



21 24 black blue pit paste heads of
sizes varying from diameter of 0.01.2
to 0.00.7 - also a number of fragments
of same



7 round paste heads diameter 0.00.7
and fragments of same.

1 paste head 0.01.3 long x 0.01.8

1 round paste head diameter 0.00.3

1 flat paste head diameter 0.00.2

2 very thin paste heads diameter 0.01.1

see page (112)

(111)

Tomb IX

From page 107

Tuesday
May 22

Four men continue digging
down floor level.

find small bits of bronze and

1 safety pin of bronze. tip to tip 0.20
width at center 0.04.

Five metal lines run across center lengthwise.

During afternoon a few more pieces
geometric bronze found at back.

Shards also geometric.

at back in a hollowed out portion is
a layer of burned earth dark gray
in color with large pieces of hard
red material - probably brick - this
layer is 0.20 thick deep.

Floor level almost reached - work with
pick stopped.

Chamber now measures 3.00 wide X 3.20
deep.

one man begins knife work.

see page (113)

From page (110)

Tomb VIII


Tuesday

(112)

May 22

During morning outline of tomb
completed - measures 3.20 deep X 4.20 wide

1 figurine appears in right section.
scale = 1 sq = 20 cm.



In afternoon work continued at right - found

7 olive pit shaped black paste heads
(broken)

4 small round paste heads and several
broken pieces.

The earth in which pots & heads are found
is very hard pressed stones.

11 pots uncovered at left rear back
7 of these in line from back wall
to center.

see page (114)


(113)

Lomb IX

Tuesday

May 22.

from page (111)



May 23

Wednesday

2 men work about one hour with knives. nothing found.

see page (118)

from page (112)

Lomb VIII

Wednesday

(114)

May 23

Two men continue cutting down earth in chamber.

on left during morning 1 skeleton in place, one skull to its left.

3 more pots and a few large bones.

on right 3 more pots and heads as follows.

31 black olive pit shaped paste heads.

16 round paste heads.

4 olive pit shaped black + white paste heads (no special pattern)

1 olive pit shape paste head
0.01.9 long. white background with black spiral motif



1 olive pit shape paste head
0.01.3 long white background with black spiral

1 reddish steatite button
0.00.8 long. bottom diameter
0.01.4


see page (115)

(115) from page (114) Tomb VIII Wednesday

May 23

all these heads ^{were} found at the right,
in no special sequence or arrangement.
During afternoon all heads left in
place.

Door cut down to within 0.30 of chamber
floor level.



In afternoon


1 steatite button (A) blue/black

0.013 long - bottom diameter 0.019

3 olive pit shaped paste heads (B, E, G)

3 round paste heads (small) (C, F, H)

1 greenish gray steatite pendant bead



(D) 0.011 long - pierced at neck

no special arrangement can be observed -
all pottery is L.H.III. There are fine
pots with fairly dark red back ground

1 pot with one wide handle has

see page (116)

from page (115)

Tomb VIII

Wednesday

May 23

the pattern and coloring of
polychrome matt painted ware -
but paint seems to be glazed.
only one skeleton in place so far,
at left, feet to door.

only 1 pot and a few bones in
niche at back

There is a small cist on line
with left side of door about
in middle of chamber (not yet
outlined)

see page (117)


(117)

Jamb VIII from page (116)

Thursday
May 24

a man work with knives cleaning
bones and pots.

Small cist beginning 1.40 fm from right
side of door outlined, measures 0.62
long x 0.27 wide. depth (greatest 0.19)



in cist are small ^{and large} skull
bones and the

following beads:

- 1 carnelian 0.01.5 long
bevelled lines 0.01.3 wide at center
0.00.4 wide at ends
flat on either side 0.00.5 thick
- 1 carnelian bead 0.01.3 long
0.01.1 wide at center
0.00.3 " " ends

- 1 carnelian bead (chipped)
0.02.7 long
0.01.5 diameter at center
slightly flattened

- 11 8 small round carnelian beads
0.00.4 - 0.00.6 diameter

- 5 4 round paste beads - largest 0.00.9 in
diameter

see page (119)

from page (113) Jamb IX

(118)

Thursday
May 24

two men working (one with knife
one with basket) - cutting lower
level of chamber. (Three men
after breakfast)

find 0.70^{-0.90} from right wall
about half way between front and
back walls the following:

- 1 small piece iron
- 1 bronze round head
0.00.6 diameter
- 2 round yellow paste beads
(broken) 0.01.2 diameter
- 1 broken carnelian head
0.02.1 long - with three
incised lines on each flat
side



- 3 small pieces bronze
deposited dots

also 8 small pieces of iron at left
back.

an iron sickle head

see page (121)

(119)

Thursday
May 24

From page (117)

Jomb VIII

1 paste head 4 leaf clover


 0.00.5 widest part.
 flat. 0.00.1 thick

These heads do not seem to have
an ordered arrangement.

at 0.15 below hip joint of placed
skeleton was found a blackish green
stone implement (?) egg shaped
0.05.6 long x 0.03.4 wide.

Skull noted on page (114) near left wall
seems to be top of skull of placed skeleton.

* this skeleton lies head to back, feet to
front of chamber, ~~back~~ back to waist.
legs turned on right side - contracted
position.

on the left of group of 11 pots back
of this skeleton, are outlined (114) more
see page (120)

From page (119)

Jomb VIII


(120)
Thursday
May 24

leg bones and 1 foot in place, are
seen; to the right of pots skull,
arm bones and ribs - this probably
is another placed skeleton, it lies
on slightly lower level than 1st placed skeleton.
Directly at left of door is a small
heap of bones (1 skull) and two pots.

1 small olive pit slope black
paste head found in angle of
one of femurs and tibia of outer
placed skeleton.

a larger cist directly in front of
door begins to be outlined.
in this cist are three skulls
and large bones.

It is irregular in outline



see page (126)

Thursday
May 24

condition found 1.00 from
right wall, 1.10 from back, 1.10
from left (on line with arch)
measures 0.32 from top to end
of handle. Handle 210 long x 0.04 wide
this layer (about 0.15-0.20 above
dromos floor) is geometric except
the camelian head.

Near camelian head found

1 reddish steatite button

0.00.9 long

0.01.5 bottom diameter

The earth at right is fairly soft, filled
with small white stones; at the back
is harder fallen stones.

a few sherds (geometric) found

1 large bone found near door.
0.22 long 0.30 in from right
side of door.
group of 12 small stones uncovered
at left wall

see page (123)

Samb LII
(Middle Helladic grave)

Thursday
May 24

Two men begin to remove
stones 5. metres west of
door of Samb XXXV and on
line with it. ^{East of right side of dromos of Samb XXXV} Stones fairly
small some flat but most
rounded.

a pot was found earlier

0.42 below top stone on

South side with a few

bones. (yellow Mycenaean) ^{page 14 C.W.B.} 50 from ^{corner} edge

at 0.20 below surface

large red painted

(amphora) pot appears (broken)

0.40 to left of side wall

toward XXXV.

neck 0.13 diameter

0.20 high

0.23 diameter

Bones + another small broken
pot (yellow with black lines)

found depth 0.45 below right
side wall. 1.00 from back wall.

50 from right ^{side} see page (124)

(123)

from page (121)

May 25
Friday


Tomb IX

3 men working - knives + bucket
these stones are fairly small
irregularly cut and placed. a

Bronze ^{spinosmiphallid} found resting on
stone at back in arch or niche.
slightly bent ^{very flat} - diameter 0.10

a cist is outlined at right, 1.20 x
0.60 (width) narrow + small
front to ^{0.30} depth = 0.15
This cist is covered partially
with small irregularly placed stones.

.45 to back wall




These stones and dramos cleaned up
So far all shards and bronze and iron found
is generic.

see page (128)

from page (122)

(middle Helladic grave)

Tomb LII

Friday
May 24

Four small pieces of bronze knife
(one with two rivets) found against
back wall depth 0.25, 0.50 from
right wall.

1. ^{shards} found 0.50 from wall 1.00 from back 0.15 from large red pit
2. pieces black steatite (parts of ^{0.07 diameter} projection of handle 0.02, 5)

1. small ^{red} pig found near bones
90 from right wall + 1.70 from
back wall.

1. coarse steatite button found
0.65 from back wall, 40 from right wall
x 0.03 wide - 0.025 long

see page (125)

(125)

from page (124) This to be known as
Tomb LII.

Friday
May 25

the cairn like structure, in front is
door. Two large stones lying on
either side and partially under the
smaller cut flat ones may be an
earlier tomb.

Squid 3 handled pot 0.08 diameter, 0.055
high, yellow background, red bands and
arrow head decoration found at depth of 0.27

0.45 from left wall, 0.30 from back wall

This early Mycenaean - others are probably
middle Helladic - ^{L.H.I} no ^{L.H.I} Mycenaean

Skull 0.20 X 0.17 (jaw and base in part) outlined
0.55 from front wall line, 0.25 from
left wall.

Present top of door is 0.23 above back wall.
Left side of chamber is 1.40 from corner
of jamb & drums (right) of tomb XXXIV.

4 tiny pieces bronze perhaps of a ring
found few centimeters to right of Myc. pot.
One sifts dirt taken out May 24

Finds one piece of bronze knife
see page (129)

from page (129)

Tomb VIII

(126)

Friday
May 25

one man sifting earth, finds

1 round paste head 0.00.8 diameter

1 " " " 0.00.9 "

2 broken bits paste

1 yellowish pendant stactite bead
0.01.2 long - pierced at neck

2 small sherds

Chambers is now ready for drawing.

and photo.

mensur 3.20 deep X 3.60 wide - check this

see page (140)

(127)

from page (97)

Jomb XXXIV

Friday

May 25

one man sifts earth from ^{front of} east door
During morning finds

1 potte head - round - 0.00.7 diameter

several sherds

1 bronze tip of arrow head (0.01.8 long)

1 obsidian ~~flint~~ arrow head (broken)

0.02.3 long

1 broken potte head cylindrical 0.01.7 long

1 obsidian arrow head 0.02.5 long

1 " " " 0.02.1 long

from page (123)

Jomb IX

Friday

May 25

Door is cut down leaving one
course - 0.15 above drums level
and 0.33 total above chamber
level.

The stones at left side of chamber
lie unevenly. ~~is not~~ wider to 0.55
0.70 at back from 0.40 at front.

see page (133)

(128)

from page (125)

Friday
May 25

Lomb LII

stones found at mean depth of 0.50

floor cleaned.

Lomb measures 2.00 wide at door
2.00 deep. sidescurve gently toward back, making a
half circle.

see page (135)

from page 43

Lomb XXXV

(130)

Friday
May 25

2 men remove door

Height 0.45
width outside 0.77
" inside 0.80
depth 0.80on left side stones is 0.17 above level
of floor - on right 0.10 above -
no fossils defined as yet.

see page (132)

Friday
May 25

Two men remove earth and stones lying directly to east between door + right wall of Tomb

III. Stones very soon reached after finding snail + track.

Small trench now begun a. 0 to east and 0.30 South of door of Tomb III on line with right large stone under door of Tomb. Stones reached at depth of 0.30.

Tomb XXXV. from page (130)

Saturday
May 26


2 men begin to dig for a dromos. Dromos impossible to determine. Space dug 2.00 South from door (including trench)

(133)

Tomb IX from page (128)

Saturday
May 26

Right list — 1 sq = 5 cm.



120 long

.80 to
right side
of door

right anterior wall

see page (134)


from page (133)

Tomb IX

(134)

Saturday
May 26.60 below wall at well
front


Tomb IX



Chamber measures 3.10 deep x 3.05

cist in drops - left side

1.65 long, 0.50 wide



1 man sifts, finds

- 1 fragment pot's head
- 1 black olive pit shaped pot's head
- 2 sherds

see page (137)

from page (129)

Saturday
May 26Tomb LII.Three
~~two~~ men.

one man in sifting finds one piece
of bronze knife, two sherds.


earth cleared from front of door.

Slab from M.H. grave XIII showed back.

The present door of Tomb LII is composed of
flat cut stones resting on two large
stones .0.40 apart. (Space goes on .0.90

from outer edge of larger stone). Door stands
including large stones 1.10 high. Smaller
stones alone 0.50. Door is 0.60 deep;
1.40 wide both front + back.

Door lies 3.20 back (north) of
middle Hallstatt grave XIII.



See page (139)

Tomb XXV.Saturday
May 26

Four men begin to clear right
side of chamber of fallen earth
and stones. Tomb dug 1927. Large
mass of earth and conglomerate gullies in.
By night have removed approximately
depth of 1.00

see page (141)

Saturday
May 26.

C. W. B. photographs

1. cist at left wall from above
2. cist in dromos from above.

In afternoon two men remove stones from left cist. Find under one of larger stones shreds of a coarse brownish pot. mycenaean?

see page (142)

Saturday
May 26.

Two men remove stones (fairly small and round) lying diagonally across right front corner of Tomb XXXVI. Loose reddish earth underneath to depth of 1.60. Hole deep measures 1.00 x 0.60.

(139)

Saturday
May 26from page (135)
Jamb. LII

C.W.B. takes photograph

a) of chambers from East (no. 2)

b) of door from South (no. 3)

see page (157)

from page (126)

Jamb. VIIISaturday
May 26

(140)

C.W.B. photographs

a) placed skeleton with group of

pots (no. 12)

b) Right heap of bones and

pots (no. 1)

1 man in sifting finds

2 1 olive shaped black head

1 round paste head

Mrs Cox begins drawing May 31

see page (165)

(141)

from page (136)

Monday
May 28

Tomb XXV -

Four men continue to dig down to floor level in right chamber. after digging down about 0.25 all over side chamber, ~~and~~ they dig down to steros in ~~front~~ ^{half} around two large stones.

a few sherds (glauconitic) found in fallen earth.

One stone flat roughly rhomboid in shape 0.80 X 0.50, set 1.20 to right of door and 0.60 back from wall removed.

a few small pieces of bronze, probably a knife, found 0.50 from right side wall, 0 from ^{adjacent} corner.

one stone rounded set into right wall about 0.80 diameter removed.

Knife work from begun.

Behind flat stone at height of 0.65 several large bones stuck out from steros. Bones measure 0.25 and 0.20 ^{long} all page (145)

from page (137)

Tomb IX

(142)

May 28
Monday

one man clears left wall cist and one man removes earth. find no fragments of pot in front, one blue paste head at back at depth 0.08.

mean depth of cist 0.15.

when stones are all removed and cist outlined, cist measures

1.60 X 0.30. the covering stones extended beyond ^{actual cist} to right and at either end.

right hand cist now uncovered steros reached at depth of 0.28 - nothing found.

cist in dromos uncovered and dug. steros reached at depth of 0.40. when dug.

cist measures 1.45 long X 0.30 at outer end and 0.27 at inner end. nothing found.

But sifted May 31 from dromos cist Tomb IX drawn & cleared June 2 sickle & bowl removed June 6

(143)

from top page (96)

Monday
May 28

Two men again clear bones which
have been covered by falling earth.
Bones lie 2.20 from right corner
wall of Tomb VIII.

Tomb 43

(144)

Four men	1 carnelian round bead	0.00.8
	1 paste round bead	0.01.1
	" "	0.00.8
	1 bronze rivet	0.01.2
	1 wavy rosette	0.01.5
found at center back.		

(145)

Tuesday
May 29

Somb XXV From page (141)

Two men clean bones in front wall
and clear fallen earth behind
large round stone removed May 28.

shaft graves

(146)

Tuesday
May 29

10 men working

Trenches E & A # 7

length 10.60

width 1.20 at north end

depth at north 1.40



2.90 from north end depth of 0.65
a stone wall measuring .60 wide
at N. narrowing to 0.15, 1.80 long
appears, another wall at it L

runs across trench, measures
0.60 - 1.00 wide, depth 0.40

a third wall runs diagonally
across trench 0.46 wide.

1.20 from 2nd at left, facing
north, 1.50 at right. depth 0.20.

stands L.H.I. III + M.H

see page (154)

(147)

Shaft graves

Tuesday
May 29

E. 816

trench #6 being dug into side
of sloping dump1. wall being outlined at north
running diagonally across trench East
west.wall previously uncovered depth
of 0.20 runs straight across
trench is 0.50 wide and lies 0.90
from west side and 1.70 from
east side of northern wall.This trench is 1.20 deep at north &
is 19.00 long. Toward South
curves to East.By now gray earth resembling that
in trench 5 + on line with it begins
at depth of 1.30.In pit in side of dump the diagonal
wall appears to have two courses only.
fine gray earth (myc. sherds)
shows at right back
see page (155) and along

Shaft graves

(148)

Tuesday
May 29E. 816 trench #5 dug 5.70 west
of trench #6 into slope of
dump. Pit containing very soft
earth and myc. ^{coarse red} sherds dug to depth
of 2.50. In this pit a number
of small round stones appear.In North section depth 1.40 1 twisted
piece bronze, 2 iron nails (?) appear.
Earth is dark gray and reddish.In afternoon a few more pieces iron
(one with prong at one end) and bronze
appear in north pit.

see page (156)


(149)

Tuesday
May 29

shaft graves

DUMR

N



E. XIX Trench no. 4 (now abandoned) lies 8.00 to west of # 5. It stops about 14.00 from beginning of slope of dump. It measures 26.00 long. at South it ends against two walls $\wedge$ (Helmstedt) and begins two other lines of wall in middle section. at the North end trench was dug to depth of 2.70 sherds myc. gray mignon and warmer unpainted ware

(150)

Tuesday
May 29

shaft graves
Trench # 3. E. XIX runs at $\angle$ of about 100° E. to west of Trench # 4, in a slight curve to the North. It is 27.00 long. greatest depth is 2.45, width averages 0.60. (widest 1.20)

sherds were

Trench # 2 runs || to Trench # 3 and 3.30 to South. It is 18.50 long, greatest depth is 3.40. a line of earth 0.60 wide was left between this trench and ^{west line cut for} shaft grave of 1925. Trench # 2 extends 5.00 to west of Trench # 3.

a ^{irregular} rectangular pit running East to west including shaft grave of 1925 has been dug || to Trench # 3. N. E. corner of pit is 4.40 from Trench # 3 and 5.80 ^{from} end of deep cutting in Trench # 4. It measures 5.60 on East side, about 9.00 on South, 7.20 on North, and about 6.00 on West side. The shaft grave of 1925 is at west end of this cutting. see page (151)

(151)

a stone wall. height 1.10

Tuesday

May 29

Shaft graves from page (150)

~~and~~ 0.90 wide divides pit into
two unequal parts, the north section
1.30 wide, the south 3.40.

The deepest part is 3.40 below surface.

Trench #1 runs (a little irregularly) E. to W.
eastern end on line ^{with} and 3.00 to south
of large ^{S. eastern} pit. It is 24.00 long.
Deepest cutting is 3.10 below surface of
ground.

Shaft graves

(152)

Tuesday
May 29

In cutting in slope, above S. Stoa
of temple several bronze rings, nails
and small discs. Shards geom. or
Corinthian. Earth fairly soft packed
with small stones.

also

badly broken paste head
bronze rivet.

see page (153)

(153)

Wednesday
May 30

Shaft graves 8 men
In cutting above South Stoa
Two men have gone down about
2.00, and are passing out of
geometric deposit.
Cutting about 1.60 x 3.00
a few myc. sherds found.
During afternoon steres found at
depth of 3.40 in center.

see page (159)

Shaft graves

From page (146)

EXIX

Trench # 7

stereos is reached in this trench
at uneven depths - from 0.90 - 1.40

A few small bones found in under-
cutting to the left (west) near northern
wall. Earth is ~~off~~ soft filled with
small stones, brownish when fresh, turns
to light
grayish when dry.

(154)

Wednesday
May 30

(155)

Wednesday
May 30Shaft graves from page (147)
E X I trench # 6

right side at depth of 1.10
next to ^{diagonal} wall, sloping diagonally,
toward outer wall. deposit is .25 deep
in back right corner gray deposit goes
down 0.20 wide and 0.30 deeper - a
cutting in red earth for wall?

In afternoon a few stones appear protruding
to south from cross wall - depth 1.40
soft earth (brown) on each side.

at 4.50 from cross wall there is
a deeper cutting in trench (slices
at 0.80) outlined on each side by
straight lines of fairly dark gray
earth - (not so dark as deposits in north
end of trench. measures 2.05 long.
see page (160)

From page (148) Shaft graves
E X I X trench # 5(156)
Wednesday
May 30

Stones running across trench are
roughly laid house walls - artificial
wall between N. + S. parts of trench
cut down as N. section becomes deeper -
at depth of 0.95 (found in N. section)
badly broken bronze bowl.

In afternoon began to find Myc. sherds
(several painted cylix stems)

see page (161)

(157)

Wednesday
May 30

from page (139)

Tomb II

Miss Cox draws tomb

- # 1 skull
- 2 L.H. 1 pot
3. knife in pieces
4. large amphora
5. yellow Mycenaean cup
6. " " jug

1 man removes pots.

(158)

Wednesday
May 30Shaft graves.
Temple terrace.

In morning two men, in afternoon
four begin new trench #108
running east to west, beginning
near S.E. corner of 5th c temple.

This is below South ramp of ^{the} acropolis.
a few geometric & proto-Corinthian shards
found. see page (162)

a sinking in earth with several
loose stones begun to be dug by two
men. This lies 18.00 north
of hut and a little to east of it.
see page (163)

(154)

from page (153)

2 men

E ~~ATA~~

slope above South Coa

Shaft graves

Thursday
May 31

Early in morning sheres found at
depth of 2.50 at left - (west) back
and 1.80 at left front.
(surface of slope very steep)

cutting measures 3.60 X 1.90 at
west end, narrowing to 0.85 at East
men transferred to pit and trench 108.

from page (155)

Shaft graves

2 men working.

stones protruding ^{South} from wall
removed - (probably fulken). Soft
earth underneath.

During day levels on each side
dug down further.


sheres - myc. some FHI

2 men

in section South of wall

depth of 0.80 below wall, two
animal bones appear.

In section between diagonal
and cross wall sheres reached
at depth of 1.40 below cross
wall and at 1.05 below diagonal
wall



see page (166)

(160)

Thursday
May 31E ~~ATA~~
trench #6Friday
June 1

(161)

Shaft graves from page (156)

E. XIX

Trench # 5 2 men working - cutting down
Thursday
May 31 northern part of trench.

By night Stereo reached at north
at depth of 2.60

Trench # 5 2 men - continue digging down
Friday
June 1 on northern section -
Mycenaean sherds.

Trench # 5

Saturday
June 2

1 narrow bronze ring
1 lead clamp 0.03.5 long



2 men continue digging down
northern part of trench -
sherds Myc. some L.H.I.

By night Stereo slopes steeply down begin-
ning 2.30 from north end
from depth of 2.20 to line of stones
probably ^{house} wall (page 156) 4.30 south of
north end of trench.

see page (170)

from page (158)
Top

Shaft graves - Temple Terrace

(162)

Trench # 108

Thursday
May 31

Four men (2 from cutting on
slope above South (Stoa) continue
to dig trench.

1/2 geometric seal stone found in

Trench - pierced on sides at center

measures 0.02.3 wide, 0.01.9 long

carved lines represent animal

Broken unevenly 0.01.1 thick at top,

0.00.7 thick at bottom.

Bits of bronze wire found

Sherds geometric, Proto-Corinthian
and Mycenaean

Friday

4 men continue trench which
now measures 36.00 long

June 1

Find glint 1 flint knife (Early Helladic?)

0.06 long 0.02.7 wide

tapering to point.



see page (167)

(163)

Thursday
May 31Shaft graves from page 158
Pit on temple terrace bottom

Two men continue digging in pit.
During morning numerous fallen
stones removed. No placed stones
found as yet. Shards geometric + mycenaean.
In afternoon rough line of stones (large
top one cut) appears. Digging begins
to east of these. By night have
dug to depth of 0.60. Earth
soft brown. geometric sherds.

Friday
June 1

Cutting East of Pit on temple terrace down
2 men continue digging to east
of large stones which now appears to
be wall. (appears also in trench 108
maybe face of foundations of altar)
Pots, scarabs found in section east of wall.



0.01.3 long, 0.00.9 wide, 0.00.5 thickest section
(back of head) - cartouche on bottom +
carving on side.

Bronze figurine 0.11 tall
shoulders 0.04.2 wide, right arm

extended forward. small birdlike head. legs 0.05
long, joined at feet. see page 164

From page (163)

Shaft graves

(164)

Friday
June 1

Cutting East of Pit on temple terrace

1 reddish steatite button
0.01.5 long, diameters 0.01 and 0.02.1
shards chiefly geometric - some myc.
1 gray Mycenaean

Saturday
June 2

2 men continue digging down
East of altar? wall. eastern
face constructed of large roughly
cut, ^{rounded} stones - top ones flat.
altar foundations 2.40 wide.
Cutting measures 2.40 along

wall, 0.70 wide and 1.30 deep

Rock reached at 1.35 - 1.45 -

men transferred to lengthening
Trench 108.

(165)

Friday
June 1

Junk 8 from page (140)

Miss Cox continues drawing
one man clears small pit finds

9 & round carnelian beads

2 round paste beads (small)

1 4 leaf clover flat paste bead E3

In squat jar #16 - gray matter (carbonized)
a bit set aside for analysis.

In afternoon finds in right hand heap

1 seal stone black 0.01.8 diameter

0.00.6 thick in middle - ribbit? on one
side, plain on other.1 seal stone red 0.01.8 diameter at
pericarp, 0.01.8 on other0.00.6 thick at center. incised on one
side, plain on other.

1 steatite spool 0.00.7 long

1 purplish pendant steatite bead

pierced at neck 0.01.2 long

1 steatite button 0.01.3 long
0.01.9 diameter

2 cylindrical paste beads

21 ~~5~~ round paste beads

1 flat thin paste bead

4 ~~8~~

olive pit dyed black paste beads

1 fluted paste head 0.01.1 long


see page (168)



Slat frames from page (160)

E. XIX trench # 6

(166)

Saturday
June 2small area directly south of
wall still being dug -measures 0.90 deep from bottom
of wall.Stones reached at 0.90-1.00 from
bottom of wall, 2.20-2.30 from top
of wall and 2.50-2.60 from surface.

(167)

from page (162)

Shift granules **EXIX**
 trench 108 on Temple terrace

Saturday
 June 2

4 men continue digging trench

find bronze bird on round standard

bird 0.03.8 high
 standard 0.00.4 "



1 broken paste scarab found in trench depth 0.15
 pierced lengthwise - cartouche on back
 measures ~~1.5~~ 0.01.5 X 0.01.

1 broken paste bead round 0.01.4 diameter

1 round paste bead (outside flaked off)
 0.01.3 diameter

1 yellow glass bead diameter 0.01.6
 thickness 0.00.7

1 yellow glass bead diameter 0.01
 thickness 0.00.5



triangular stone head black + white

see page (169)

from page (165) Tomb 8

(168)

In uncovering front cist two
 more skulls appear.
 also find in front cist

Saturday
 June 2

4 olive pit shaped black paste beads

8 round paste beads

4 fragments

1. white olive pit shaped paste bead
 0.00.7 long

1 blue black steatite button
 0.01.2 long
 0.01.4 diameter

1 round carnelian head diameter 0.01.7
 " " " " 0.00.3

1 flat steatite ^{bead} ~~button~~ green gray
 pierced at one side
 diameter 0.01.1
 thickness 0.00.3

front
 as cist is cleared it changes and
 becomes three 

1 man continues clearing ^{front cist} ~~that~~ uncovers Monday June 4

3 pots 4 skulls (2 on June 2)

1 steatite concoid button 0.00.8 long
 0.01.6 diameter

1 terra cotta double concoid button
 0.02 long
 0.02.2 widest diameter

1 4 sided steatite button 0.01.1 long
 width of side 0.00.5

skull of back placed skeleton measures
 0.18.4 long X 0.13.3 wide
 2 more into uncovered in clearing out bones see page 19 Book II

(169) from page (67) Temple Trench #108

Monday Shift graves. 8 men

June 4 Several large stones appear in Trench
4 m. from face of altar. They
later prove to have only loose earth
under them. Ramped -

shards, glass, myc. & bits of bronze
at greatest depth just east of altar wall trench is
now 1.40 deep.

west of altar wall find depth 0.80

1 plate head round 0.01 diameter

2 " " head round 0.009 " (broken)

at depth of 0.90 and at 8.00 west of altar
wall a ^{several} ~~plate~~ large flat stone appears.

at west end of trench ^{large} pot (burned in situ)
stones then outlined across trench



on both sides of altar depth of 1.20 on
west side, 1.40 on east numerous middle
Helladic shards appear mixed with myc.
late in afternoon in west end of trench
appears a flat stone, next to it another
narrow cut stone with two thin edges.
depth 1.50 see page (172)

from page (161) Shift graves E 81X trench #5 (170)

2 men working going down

on each side of wall across trench

which is 3.00 deep at wall.

stones reached at 3.20 - 3.40 below

surface & two men transferred to

temple trench #108.

Monday

June 4


In section of trench
farthest east there find geminite
shells; in next section ^{to west} a mixture
of geminite & mytiloid, and near
shore mostly mytiloid.

(173)

shaft graves

Tuesday


June 5



1 sq = 1 meter

shaft graves

(174)

Tuesday
June 5

Hollowstep at end

(175) Kam page (172) Shaft graves
Temple trench #108

Wednesday

June 6

10 men working

Laid stones near drain are probably
a house. Myc. cyles found (broken)

also a few animals bones depth 1.40

Large cooking pot found depth diameter

Terra cotta drain is 0.16 wide 0.06 deep
extends 0.66 diag. across trench from corner
going S.E. Drain is at depth of 1.60

Continuation of drain is line of stones
corner stone (?) of house is flat; corner is
depth of 0.65 below corner stone + 1.70

below ground surface ^{and} smaller, some
cut, some rough.

Drain runs into lower course of stones

0.35 high roughly triangular in shape

During morning all these + stones to East
cleaned up.

In middle section greatest depth is 2.50

Middle sect. In afternoon many shreds of grey mycena
appear depth 2.70 -

near line of large rough stones a

series of 6 small stones appear depth
as page (176)

Shaft graves. Temple trench #108

Kam page (175)

2.00 sloping little to west

and at depth of 2.40

large flat stone outlined, sloping
west to east. Stone measures 0.60

along Trench X. 0.62 (width of Trench)

Earth very soft with some small

stones, changing to gray. Along Trench

several large evidently unworked stones
protrude from sides.

For two metres from flat stone west - earth

very dark - greatest depth ^{now} 3.30

See page (177)


(176)

Wednesday

June 6

(177) from page (176)

Sample trench # 108
Thursday
June 7 6 men working *



scale 1 sq = 10 cm.

foundations of house

highest stone = 90 below surface

bottom 1.50 below surface

see page (181)

Tomb 52 III. Summary

(178)

Tomb 52 lies 5 m. west of Tomb 35.

The left side of chamber is 1.00 East of right drinos wall of Tomb 34, the back wall 1.40 from right front corner of Tomb 34 see floor level is 1.40 above the floor level of Tomb 34.

The door is 3.20 back (width) of middle Helladic grave XIII.

The door is composed of two large round stones 0.40 apart which support small cut flat stones laid irregularly. The top course is fairly flat, however, going down a bit to the East.

The door is 1.10 high including large stones, smaller ones above 0.50 high. It is 1.10 wide both front + back + deep.

No ceiling is preserved.

The chamber measures 2.00 wide x 2.00 deep, sides curve ^{to back} forming a half circle. Parts of the side walls (near door) were destroyed by the trial
see page (179)

Tomb 52 LII from page (178)

trench which uncovered one yellow Mungon jug, one skull and a few bones.

The floor is 0.50 below surface at back and at front of chamber.

at the left front of chamber were one skull and a few bones.

at the left back (depth 0.27) a small squat jar with three handles, comma decoration L.H.I. yellow background, red red bands & commas.

at the back of chamber were found

- 6 pieces of a bronze knife
- 4 pieces of a ring
- 1 steatite conoid button.

at the right a large amphora - L.H.I?

near it were a few bands and to its left a small ^{shallow} cup (yellow background with black paint)

at the front on right side were found a small red jug and a yellow Mungon goblet.

There were neither cuts nor placed skeleton.

see page (180)

from page (179)

This tomb although at a high level (1.40) above Tomb 34 contained ^{some} subjects of an earlier date - L.H.I and yellow Mungon pots.

Inventory

- 1 steatite conoid button
- 6 pieces bronze knife
- 4 pieces bronze ring
- 1 skull
- 5 pots.

when door ^(small flat stones only) was removed (June 8)

a third large stone was exposed standing between ^{the} two others and 0.90 back of the front line. This third stone measured 0.45 high and 0.50 wide & 0.55 long.

(181)

from page (177) Temple. Trench #108

Thursday
June 7

Four men continue to dig down through black earth which is now mixed with streaks of red on sides. Slices on north side of trench:
Middle Helladic sherds.

In section nearest ramp find:

stone implement roughly cut octagonal concoid shape with smaller stem at one end. measures 0.12 long x 6.50 stem 0.025 long x 0.028 wide



C.W.B. takes pictures of

1. House from west ho. 5
2. " " pit " 9
3. Drain " 10
4. Trench from altar foundation facing East (ho. 11)
5. Trench facing west showing altar face (12)

Trench 108 maybe divided into 3 sections

1. from west end to west face of altar

in this the drain & myc. house foundation a 2nd level of drain protrudes a little from corner of Trench 2, 2.8 above the other 8 m. long

(182)

foundation of altar extend 3.50 along it -

2. 2nd or middle section from E. face of altar to line of large lovely

* excavated stones - length 15.40

- 3rd section curves a bit to north

measures 14 m. it ends 2 m

from N.E. corner of steps cut into conglomerate of a terrace.

Trench at west end is 4 m.

E. of foundation of Temple.

- * at eastern end this section has at depth 2.00 a series of rough round stones, at 2.40 2 large flat stones (cut).

at 3.30 depth ^{run} 2 m. west

from flat stones earth black thickness of stratum 0.30-40.

Below this, a narrow long hole goes down. measures when

clear. 2.30 x 2.00 at narrow end + .80 wide

stones rise in trench from this depth ^(3.30) to west at 2.10 depth

in a series of shelves protruding from
north side of trench starting across it.

14.50 from altar
depth 2.00
Trench varies in width from
2.60 wide to 1.05

13m from altar

flat stone
depth 2.20

depth 2.40
4.30 from altar
deep
3.80 deep

steps 3.20
9m from altar

steps 2.30
7m from altar

steps 1.80
4m from altar

steps 1.90
altar

In eastern section by night
greatest depth = 2.10
not shallow = 0.80

see page 20
Book II

1. Skull

2. [] L.H. 1

3. Knife in pieces

4. Large angular

5. yellow mung up

6. " "

skull - M.H. in place - front bone smoothed
measures front to back .14.9 (in place)
side to side (not even - vacuum only) .12.9
later 13.03

Skull in # 16? in M.H. Cleveland
front to back .18.8
top of jaw to back .22.6
" " to top of skull .19.2
" " to top of nasal cavity .14.2

18.4 long

176
48
224

16 ashes?
squat 3 huddled

